Jefferson Lab MAGNET GROUP

16th July 2019 v1.00 Ruben Fair on behalf of

Probir Ghoshal, Sandesh Gopinath, David Kashy, Renuka Rajput-Ghoshal, Eric Sun, Randy Wilson, Dan Young

Outline

Contribution to Physics Division and Project Involvement

- Hall A
- Hall B
- Hall C
- EIC
- Cryo
- HD Ice
- MOLLER
- Other Work
- Publications
- Support for DOE reviews
- Team Strategic View

HALL A

Dan Young

SBS GEn

Super BigBite Spectrometer Target Magnetic Field Shielding



The target is polarized 3He inside a magnetic holding field produced by a pair of Helmholtz coils.

- > The shielding eliminates fringe fields.
- It is double walled in order to reduce the amount of material needed for this shielding as it reduces the strength of the field as it crosses the gap between shielding walls
- Shielding plates are 1008 Steel



Designed and modeled Double Wall Floor Panels at the corners of the Target Magnetic Field Shield where it overhangs the pedestal deck.

Pedestal Shielding Plates Typical for the underside of entire pedestal

Designed and modeled shielding plates for the underside of the pedestal to simulate the double wall shielding of Target Magnetic Field Shield **Probir Ghoshal**

Torus – Modeling of the magnetic field

Modeling the actual conductor layout for the torus magnet in Hall B to improve matching with the measured field data

- Step 1 Actual averaged data from all coils significantly improved the comparison (0.05% at 46.5 cm on radius and 0.5% on 30 cm radius)
- □ Step 2 Varying the thickness of the modeled coils close to the hub near the bends
- Bulge the coil corners outwards (both DS and US ends) by 2 mm – results did not match field measurements sufficiently well.
- Theory postulated that perhaps the hub welds were magnetic. This was modeled and residual magnetism measurements were carried out – results were inconclusive
- Compress coil corners inward by 8mm only on the DS end of the torus coil near the hub – Mapping data provided, Physicists are reviewing the calculation results





Downstream Beamline

Investigate and document As-Built condition Investigate pipe configurations for future experiments





EMC-SRC Detectors Detector mounts/positions to clear future experiments Detector mounts to clear existing cable trays







Structure is shown at SHMS min angle of 5.5°

Investigated and provided information regarding the particle path thru the Bender Magnet shielding as well as the location of the lead and tungsten shielding with the SHMS at min angle



Optimization of SHMS Magnet Dump Resistors

- Existing 75 mΩ dump resistors of SHMS Q2/3 and Dipole triggered quench-backs and induced long recovery time (Fig. 1) and high temperature rise (Fig. 2) with fast discharges from high currents.
- Fig. 3 shows that the critical currents of Q2/Q3 magnets are always larger than the decay current with 7.5 mΩ dump resistor. Fig. 4 illustrates the Dipole's critical current is always larger than the decay current with a 25 mΩ dump resistor. No quench-back is expected for both of them.
- 7.5 m Ω and 25 m Ω dump resistors, manufactured by Switzerland's Widcap AG, are now here at Jefferson Lab.
- Test schedule of modified dump resistors: early August 2019. Cryogenic impact to other Halls is not expected. Test currents will be 3660 A (Q2) and 3450 A (Dipole).
- Journal Paper: Quench-back Management for Fast Decaying Currents in SHMS Superconducting Magnets at Jefferson Lab
 - Accepted with minor revisions by IEEE Transaction on Applied Superconductivity Journal
 - Submitted the second revision on June 26, 2019.









EIC

Renuka Rajput-Ghoshal

Magnet Design

 Preliminary design completed for all quadrupoles, skew quadrupoles, solenoids, corrector magnets for Ion and Electron beam lines in the interaction region for the updated lattice file for higher COM energy.

- Updating the Interaction Region magnet design part of the p-CDR, magnet design section has been updated, magnet interaction and shielding work is in progress.
- Investigating design options for 7.6 T cooling solenoid (1 x 1.25 m long, 5 T; 1 x 2.5 m long, 7.6 T) and other ICR magnets (revisiting the coil length of magnets to fit into a 11.4m cryostat).



CRYO – ESR2

Dave Kashy

- Preliminary Design Review held June 19
- Team on the right path and making good progress
 - Cycle work
 - Max CHL support needed is 5g/s
 - 15K, 12K and 8.4K target supply temperatures all being incorporated with two and one time possible
 - 4K supply and return as now but more capacity
 - Building layout
 - Well along in hardware selection and location
 - Significant thought has gone into developing designs for safety and reliability and maintenance
 - Need to do hardware testing and refurbishment
 - Leak test the cold box near future
 - Compressors maintenance and testing by a specialized vendor planned



HDIce

HD Ice Dump Solenoid (UITF)

Dave Kashy



New project

 Required by the HD Ice
 Team to enable focusing of electron beam





Dave Kashy

HD Ice Dump Solenoid

- New project
 - Multiple versions analyzed
 - Power supply identified and loan agreed to (spare from DC power group), EPICS programming complete, 480V welding outlet connection installed (plug and play)
 - This set the design parameters for the winding
 - Magnet needs to be operational in UITF by 9/30/19
 - Procurement plan: JLab to order major materials and have mandrel (spool) built, get a vendor to insulate/wind coil on mandrel

Parameter	Unit	Value
Bore	mm	254
Length	mm	500
Current	Amp	342
Voltage	V	43.2
Conductor	mm x mm x mm	10 x 10 x 7.5 id
LCW Flow	gpm	3







HDIce

HD Ice Dump Solenoid

Z=3000 mm

- New

- NewLin

Opera

3,50

2,500

2,000

Probir Ghoshal



MOLLER

Ruben Fair

Spectrometer CD0 to CD1 Action Plan

LER SPEC	TRO	DMETER					BUDGET	ARY ES		ES REQUI	RED BY E	ND SEP	T 2019 Fe	or:
CD1 Action	n Pla	in					DS Coils			DS Coil Str	ongbacks/	irame/encl	losure	
		Version No.	8.00				US Coils							
		Date	07.10.2019				Power Sup	oplies						
		cc	MOLLER Spectror	neter Team, Ro	bin Wines		Beam pipe	i -						
							Collimator	rs 1 and 2						
								Budgetar						
								у						
							Conceptual	estimates			Pre-			
							Design	by End	JLab		submission			
							Report /	Sept /	Level 2	Independent	review of			
							Quantify	l echnical Referen	Cost and	Cost and	Conceptua			
						BOE	Risks	Boulows	Baulau	Region	Report			
		Task	Vho	Mau-19	Jun-19	Jul-19	Aug-19	Sep-19	Oct-19	Nov-19	Dec-19	Jan-20	Feb-20	Ma
	1	PROJECT MANAGEMENT												
Director's														
ReviewApr	11													
2019 -		Constructed and the second standard structure of the standard structure of the structure of	D.L.					-						
Recommendatio Director's		Lomplete and document the engineering analysis and cost estimates of the coll options	Huben				STARTE	U						
Review Apr		Complete and document the engineering analysis and cost estimates of the vacuum vs.												
2019 -	1.2	helium gas choice - weighing the risks to other parts of the apparatus. Commit to one												
Recommendatio		design	Ruben/Team					START	ED					
	1.3	Timeline for work performed by collaboration	KK/JM/Ruben		COMPLET	Е								
	1.4	Establish Initial Basis of Estimate	Ruben		COMPLET	Е								
	1.4.1	Provide Basis of Estimate (BOE) codes to PM	Ruben	COMPLET	E									
	1.4.2	Provide justification for BOE codes and task descriptions to PM	Ruben	COMPLET	E									
	1.5	Assess risks - set contingency	Ruben					START	ED					
	1.6	Level 2 - Cost and Schedule Reviews	Ruben											
	1.7	Prep Independent Cost Review	Ruben											
	1.8	Project Independent Cost Review	Ruben											
	1.9	Prep for CD-1Review	Ruben											
	2	CD-1Review	Ruben											
	2.1	DOE CD-1Process	DOE											
	2	SPECIFICATIONS / DESIGN QUESTIONS												
	2.1	Complete and add to 'Specifications Table' <i>[Ref. Document A below]</i>	Ruben											
	2.2	Obtain answers to 'Design Questions' <i>[Ref. Document Chelow]</i>	Ruben											
	2.3	Address 'Design Questions' <i>(Ref. Document C below)</i>	All											
	3	BEAM PIPE DESIGN												
	3.1	Beam pipe design (Helium option)	Dave			START	ED							
	3.2	Beam pipe design/prototype	Dave		STARTE	D								
	3.3	Vindow for exit to detectors (design for yac or for helium or both??)	Dave											
	3.4	Beam pipe support design	Dave											
	3.5	Helium tube design downsteam of the DS torus	Dave											-
	3.6	Make a crude model of the beam nine that goes through the toroids	Dave			START	ED							
	v													

MOLLER

Ruben Fair

- □ Basis of Estimate complete
- Down select of DS Hybrid v Segmented coil design underway

	Pugh Decision Matrix			-					
	Project	MOLLER	R - DOWNSTR	REAM TOR	US				
	Sub-System	Magnet	t Coils						
	Version No.	3.00							
	Version no.	7 10 2019							
	Engineeric	D Esiz D 0	Shochol D. Kochi	S Coninath	P. Wilson				
	Ligneens	n. rai, r. c	priosnal, D. Kasn	y, o. oopinadi,	n. wiison				
	Natas	(a) Headaa	'W/RDID' antian	antes BASEL		ON to compare pasing)			
	notes	(a) Use the	- 4 interleaved of	as the DAJLE	INC OF I	Com to compare against.			
		(D) TH DRID	ATED 4	ub-coils					
		(C) SEGME	NTED = 4 separat	e sub-colls					
				ALTERNA	TIVE				
	Criteria (Critical to Quality)	Criteria Rating or Veight (1 - 10)	HYBRID (BASELINE)	SEGMENTE D		JUSTIFICATION FOR SCORE COMPARED TO BASELINE			
_	DESIGN	<u> (· </u>							
	Satisfies all physics optics requirements	10	0	0		Confirmed by JM that both designs satisfy physics requirements			
	Minimal local magnetic 'anomalies' (e.g. near transitions and lead in/out)	5	0						
	Lowest operating current	6	0	-1					
	Lowest operating voltage	6	0	-1		Segmented subcoil 4 has the highest voltage			
	Lowest temperature rise	6	0	-1					
_	Lowest water flow velocity	6	0	-1			_		
-	Lowest pressure drop	9	0	1					
-	Readily available conductor	6	0	-1					-
-	Lowest cost power supplu	6	ő	-1		Segmented subcoil 4 voltage requirements drives up PSU cost			
	Lowest number of soldered joints	5	0						
	Lowest number of electrical isolation breaks	5	0						
	Minimal technical complexity of coil design	6	0	1					
	Lowest cost of coils	6	0	1		Based on budgetary estimates from vendors			
_							07		
_	FIRDIO ITION						-21	DESIGN	
-	FADRICATION Eace of conductor cleaning prior to winding	3	0	0					
-	Ease of insulating conductor immediately prior to winding	3	0	0			1		
-	Ease of bending conductor during winding	5	0	1		Fewer out-of-plane bends for segmented coils	1		
	Minimal risk of damage to conductor inner channel during fabrication	8	0	1		Fewer out-of-plane bends for segmented coils	1		
	Ease of controlling coil dimensions during insulation and winding	8	0	1		Fewer out-of-plane bends for segmented coils	1		
	Reduced complexity of winding tooling, jigs and fixtures	6	0	1		Fewer out-of-plane bends for segmented coils			
	Ease of handling	6	0	1					
	Reduced complexity of potting mold and any necessary fillers	6	0	1		Fewer out-of-plane bends for segmented coils	-		
_	Colls are easier to pot (less tortuous resin flow paths)	6	0	1		rewer out-of-plane bends for segmented coils	-		
-	Reduced size or curing oven Coils are easier to cure (reduced temperature gradient across cross-costion)	6	0	1		Erwer out-of-place bends for segmented coils	1		
-	Ability to maintain turn placement during winding		0	1		Fewer out-of-plane bends for segmented coils	1		
_	Ability to maintain turn placement during potting	8	0	1		Fewer out-of-plane bends for segmented coils	1		
	Ease of fitting water and electrical connections	6	0	0			1		
	Ease of joining power busbars to coils	6	0	0					
	Ease of fitting temperature sensors	5	0	0					
_	Ease of carrying out dimensional checks	5	0	1		Fewer out-of-plane bends for segmented coils	-		
_	Ease of performing other QA/QC checks (flow, resistance, hipot)	5	0	0			-		
-	Lase or transport from vendor to viab	,	0				1		
_							82	FARDIC	ATION
_								1. nonio	

\Box FMEA underway \rightarrow Risk Register

		FAILU	RE	MODES AND EF	FEC	CTS .	ANA	LYSIS (FMEA)				
	Project	MOLLER Spectrometer										
	Version No.	1.00										
	Date	06.21.2019										
	Engineer/s	R. Fair, P. Ghoshal, D. Kashy, S. Gopin	ath, R	R. Wilson								
		SEVERITY (S) = What is the impact on perform	nance	?								
		OCCURENCE (O) = How frequently could this	happe	en?								
		DET (D) = How likely are we to detect it?										
		Risk Priority Number, RPN = S × O × D - Aim f	or an F	RPN which is lower than 'a' below]								
		Max. RPN = 6 (S) * 5 (O) * 6 (D) = 180										
		RED = RPN ≥a	45									
		YELLOW = b < RPN < a	40									
		GREEN = RPN < b	10									
		UNCER - REH S D										_
				MODK	снее	т				l		
				WORN	JILL			_	1			
							_	.= e		2 2		
	Pow	5					lön	2 2		citio	l ë	
	2	5		ŝ		E.	iga	5		d A	iga	
	ail.	Ě.		ing .	•	ē,	٤Ē	털			1	
	a a	a	>	ial O	enc	<u>5</u>	li fe	e e	5	Ē	Ę	
	E H	Iure	ie iit	ti a	1	ig at	N (E	é e	ect.	L. Log	S Z	
	Pot	Fai	Set	Pot	ö	2 H	2 S	E C	Det	Rec	- E	
	Leak of H2 into coil space	Pacshen voltage breakdown damaging coils and surrounding structure	6	Leak from target into coil space via beam line	3	5	90 🥥	Physical barrier (window?) between target and coil space	2		•	36
ł	Leak of air into coil space	Pacshen voltage breakdown damaging coils	6	Leak in vacuum seals			0				•	0
ł		and surrounding structure		Insufficient insulation or insulation							-	
	Short between coils	Damage to coils, unbalanced magnetic field	6	damage during fabrication, transport or assemblu			• •				•	0
ł		Damage to coils and surrounding structure		Insufficient insulation or insulation			_				-	-
	Short between coil and Ground	unbalanced magnetic field	6	damage during fabrication, transport or assemblu			0				•	0
t		Coil damaged during handling, transport,		Incorrect enoxidalass cloth			_				-	
	Modulus of VPI'd coil too low	assembly or during during operation due to a fault scenario with unbalanced forces.	6	combination, bad potting			• 0				•	0
ł											-	
	Modulus of VPI'd coil too high						0				•	0
I	Radiation damage to coil noses	Coil insulation and structure degrades ultimately causing a coil failure	6	Incorrect epoxy, higher than expected radiation dose			0				•	0
ł	amage to coils during fabrication	Coils are unuseable in the worst case or in	-	Incorrect epoxy/glass cloth							-	
	at vendors due to difficulty in handling 'floppy' coils	the best case take a long time to repair.	5	combination, bad potting, poor handling fixtures or procedures			0					U
1	Magnet coil water cooling loops	Coils are unuseable in the worst case or in		Poor quality control, less than clean			• •					
	get blocked during fabrication	the best case take a long time to repair.	9	rablication enviroment, poor manufacturing practices								
Ī	Magnet coil water cooling loops	Coils are unuseable in the worst case or in	F	Poor quality control, less than clean			• •				0	
	get blocked during assembly	the best case take a long time to repair.	9	assembly practices			•••				×	°.
Ī				Poor water quality, poor filtering, debris from water chiller construction								
	Magnet coil water cooling loops	Coils are unuseable in the worst case or in	5	makes its way to coils, cooling			0				•	0
	get blocked during operation	the best case take a long time to repair.		channel erosion due to tight bends and higher than designed water flow			-					
+	Coils move out of slignment	Spectrometer is unuseable in the worst open		rates								
	during operation due to Joule	or Physics acceptance is reduced in the best	4	Coils expand and move due to heating during operations			0				•	0
+	heating	case Spectrometer is unuseable in the worst case		Coils move due to vacuum chamber					-			_
	Colls move out of alignment during vacuum pump down	or Physics acceptance is reduced in the best	4	walls moving during chamber pump			0				•	0
ł	Coils move out of alignment due	Spectrometer is unuseable in the worst case		uown							-	
	and the second sec	and the second second second second second line also be set		Colle ese under arquitu						1	100	



Ruben Fair

Down select of Helium v Vacuum environments underway



JLab team assisting with this task

MOLLER

Dave Kashy / Randy Wilson / Sandesh Gopinath

Magnet Designs

- Optimized coil designs for upstream magnet and two designs for downstream magnet, hybrid and segmented.
- All designed for 100psid LCW
- All meet all pre-set specs for current density and temperature rise
- All designs have simpler winding designs compared to previous designs

Upstrea	m		000000
Upstream Torus Feb 26, 2019			US Torus (single pancake)
LUVATA Conductor #			6862
Conductor width	w	mm	8.2
Conductor width	н	m	7.2
Concuctor hole dia	d	mm	5.0
Insulated Coil Clearance to envelope	С	m	2.5
Ourrent Density	Rhoi	A/mm2	18. 5
Temperature rise	DT	С	27.9
Water velocity	V	ft/sec	9.4
Water Pressure Drop	DP	psi	100.0
Subcoil String flow rate	F	gpm	6.2
Voltage Subcoil String (PS voltage)	<u>v</u>	V	61.5
Current Subcorr Scring (PS current)	-	A	714.3
Power Subcoll String (PS power)	P	KVV	44.0
Total Magnet Power	PT	kW	44.0
Total Magnet Flow rate	Fm	gpm	6.2
Average temperature rise	DT avg	С	27.9
Pump DP	Н	psi	100. 0

DS Segme	nte	d	00000	0 0 0 0	0 0 0 0 0 0 0 0 0 0	O O O O O O O O O O O O O O O
Segemented Torus Feb 25,2019			DS segmented Sub	DS segmented Sub	DS segmented Sub	DS segmented Sub coil 4
-			co11 1	co11 2	co11 3	
LUVATA Conductor #			7034	8426	8151	8193
Conductor width	w	201201	12.7	14	15	16
Conductor width	н	171271	12.7	14	15	16
Concuctor hole dia	d	201201	4.5	6	7	12
Insulated Coil Clearance to envelope	c	mm	4.5	14.8	23.9	-0.6
Current Density	Rhoi	A/mm2	15.4	12.2	10.4	14.7
Temperature rise	DT	С	23.0	14.6	17.8	28.1
Water velocity	V	ft/sec	14.0	13.2	10.9	9.5
Water Pressure Drop	DP	psi	97.2	99.1	99.2	98.5
Subcoil String flow rate	F	gpm	7.5	12.6	14.2	72.6
Voltage Subcoil String (PS voltage)	V	V	19.7	22.9	33.0	246.1
Current Subcoil String (PS current)	I	A	2228.7	2032.1	1939.1	2095.9
Power Subcoil String (PS power)	P	kW	43.8	46.6	64.0	515.8
Total Magnet Romer	DT	ъw	670.2			
Total Magnet Flow rate	Fm	dina.	106.9			
Average temperature rice	DT aser	3 Per	24.8			
Draw DD	u	-	21.0 09.5			

DS Hyb	rid		00	00	0 0 0	0 0 0 0 0 0 0 0 0 0 0 0
Hybrid Torus March 6,2019			DS hybrid Sub coil 1	DS hybrid Sub coil 2	DS hybrid Sub coil 3	DS hybrid Sub coil 4
LINATA Conductor #			10000	9.449	8185	6819
Conductor width			13.0	13.0	13.0	13.0
Conductor width	н	1100	13.0	13.0	13.0	13.0
Concuctor hole dia	d	2025	8.5	6.0	9.0	10.0
Insulated Coil Clearance to envelope	c	1121	4.5	15.8	25.9	5.7
Current Density	Rhoi	A/mm2	17.4	10.2	15.0	13.9
Temperature rise	DT	C	19.2	16.3	20.4	11.7
Water velocity	v	ft/sec	12.8	11.1	10.7	11.0
Water Pressure Drop	DP	psi	99.4	99.4	99.5	99.8
Subcoil String flow rate	F	gpm	49.1	10.6	23.0	58.4
Voltage Subcoil String (PS voltage)	v	V	123.3	30.8	75.9	140.5
Current Subcoil String (PS current)	I	A	1938.0	1425.0	1565.0	1230.0
Power Subcoil String (PS power)	P	кw	239.0	43.9	118.8	172.9
Total Magnet Power	PT	КW	574.5			
Total Magnet Flow rate	Fm	gpm	141.1			
Average temperature rise	DT avg	C	16.1			
Pump DP	н	nei	99.5			







SECTION VIE

MOLLER Dave Kashy / Randy Wilson

Collimators 1 and 2

- Complete redesign (design) of collimators 1 and 2 for Moller
- Mating C1 and C2 eliminates possible alignment errors
- New design creates less background and has simpler water cooling connections
- All parts detailed to obtain updated cost estimates
- Helium to Vacuum window designed and some prototype welds attempted, E-beam welding is next, brazing an option
- Final design must wait until we get the heat load distribution along the length
- Invention disclosure of "Ultra-Compact Pipe Coupling" submitted

Weld demonstrator











MOLLER

Dave Kashy

Beam Pipe

- Preliminary Design for helium pipe completed to allow simulations
- Materials for design confirmed available
- Weld demonstrator complete and successful:
 - 0.035" x 0.065" tube walls
 - Straight and leak tight



MOLLER

Magnet Coil Thermal Analysis

- Sandesh Gopinath
 - **Objectives**: To understand thermal stress distribution in Moller Magnet coils, to estimate coil motion and shear stress in the coil insulation





Sandesh Gopinath

Magnet Structural Analysis

Utilizing ANSYS & MAXWELL

(magnetic field calcs from MAXWELL are a good match with results from OPERA)

US Torus - ANSYS structural (gravity + mag forces)



SLAC LCLSII + Test Lab

Randy Wilson

Final design task for the SLAC LCLS II project was a pair of seismic rated Gas Analyzer Cabinets. Fabricated at Jefferson Lab.

Developed model and drawing of access ladder for test lab project .



Other Work

Dave Kashy / Ruben Fair / Probir Ghoshal / Renuka Rajput-Ghoshal

- *Ruben/Probir:* Hall B SC Magnets punch list: >90% completed
- **Dave:** Hall B Torus burped and warmed to 80K by D. Insley following the written procedure and no changes were required
- Dave: Hall B Solenoid helium level unstable, had techs pump u-tubes and solved
- **Renuka**: Involved in the Hall C NPS Experiment Readiness Review
- **Renuka**: Involved in the review of Injector solenoid spare coils/magnets
- Dave: Did preliminary cooling calcs on raster magnet for Jay Benesch
- Dave will be presenting an 'Introduction to Cryogenics' talk to the Graduate Students at the August 21 Pizza Luncheon
- **Dave**: Still working to get folks to communicate about cryo operations using the <u>esr-users@jlab.org</u> e-mail list, latest examples of missed communication:
 - Cryo did not communicate the 15K supply U-tube failure until prodded
 - Hall C target cool-down not communicated even after HCLOG was updated

Other Work

Eric Sun

Mechanical Analysis of Coil Novel Gasket-based Nonlinear Analysis of Superconducting Magnets

1.2E+08 ---- FEA results (insulation is modeled with -0.15 mm gaskets) 1.0E+08 thick gasket 8.0E+07 Gaskets can simulate Stress (Pa) 0.3 mm 6.0E+07 complex strain-stress thick gasket relationship. 4.0E+07 2.0E+07 Difference = 0.78%1.525 mm 0.0E+00 thick SC cable 0.00% 0.10% 0.20% 0.30% 0.40% Strain (%)

- To better predict the overall stress/strain of a coil, a more accurate analysis method is needed.
- Present analysis methods assume the coil as either linear isotropic or linear orthotropic, which is far from reality.
- Gasket-based nonlinear analysis is the first of its kind to use the stress-strain curve of a 10-stack Nb₃Sn coil sample as an input to the nonlinear analysis.
- To implement it, the gasket material property is obtained by subtracting the property of the SC cable from the stress-strain curve of a 10-stack coil sample.
- Stress-strain relationship is computed using a 10-stack coil model (with gaskets). The FEA result is then compared with the test results to validate the property of the gaskets.
- The new method can improve the accuracy of the analysis by up to 45 times depending on the layer granularity of the model.
- → This type of analysis could prove to be crucial for designing high field magnets employing Nb₃Sn superconductor (EIC, Hi-Lumi, FCC......)

Other Work

Dan Young

Coil Structure Modeling

(with Eric Sun)

Modeled and modified coil components to reflect a variety of iterations to aid in engineering analysis and simulations



YC

Publications / Conferences

1. Manuscripts Published and under review/accepted

- Mark Wiseman , Chuck Hutton , Fanglei Lin, Vasiliy Morozov, <u>Renuka Rajput-Ghoshal</u>, "Preliminary Design of the Interaction Region Beam Transport Systems for JLEIC" ", IEEE Trans on Appl. Superconductivity, V29 (5), August 2019
- R. Rajput-Ghoshal, R Fair, P K Ghoshal, C Hutton, E Sun, M Wiseman,, "Conceptual Design of the Interaction Region Magnets for Future Electron-Ion Collider at Jefferson Lab", IEEE Trans on Appl. Superconductivity, V29 (5), August 2019
- E Sun, P K Ghoshal, R Fair, S Lassiter, P Brindza, "Quench-back Management for Fast Decaying Currents in SHMS Superconducting Magnets at Jefferson Lab", IEEE Trans on Appl. Superconductivity (Accepted, June 2019)
- P. K. Ghoshal, D. Chavez, <u>R. Fair</u>, <u>S. Gopinath</u>, <u>D. Kashy</u>, P. McIntyre, T. Michalski, <u>R. Rajput-Ghoshal</u>, A. Sattarov, "Preliminary Design Study of a Fast-Ramping magnet for Pre-concept Design of an Electron-Ion Collider at Jefferson Lab", *IEEE Trans on Appl. Superconductivity* (Accepted, June 2019)
- V.S. Morozov, R. Ent, Y. Furletova, F. Lin, T.J. Michalski, <u>R. Rajput-Ghoshal</u>, M. Wiseman, R. Yoshida, Y. Zhang, G.L. Sabbi, Y. Cai, Y.M. Nosochkov, M.K. Sullivan, "Full Acceptance Interaction Region Design of JLEIC", presented at 10th International Particle Accelerator Conference (IPAC'19)

2. Preparation in Progress for Submission to Magnet Technology (MT26) Conference (Vancouver, Canada) – Sept-Oct'2019 and NAPAC- Sept 2019

- <u>R. Rajput-Ghoshal</u>, <u>R. Fair</u>, <u>P. K. Ghoshal</u>, "Optimization of the Interaction Region Quadrupole Magnet for Future Electron-Ion Collider at Jefferson Lab, Accepted ORAL Presentation, IEEE Trans on Appl. Superconductivity
- E Sun, P Brindza, <u>R Fair</u>, <u>P K Ghoshal</u>, S Lassiter, "Test Results of Quench-back Management Due to Fast Decaying Current and AC Losses in SHMS Superconducting Magnet at Jefferson Lab", Accepted POSTER Presentation, IEEE Trans on Appl. Superconductivity
- D. Kashy, R. Fair, P. K. Ghoshal, R. Rajput-Ghoshal, "An Investigation of the Electromagnetic Interactions between the CLAS12 Torus & Solenoid Superconducting Magnets at JLab", Accepted POSTER Presentation, IEEE Trans on Appl. Superconductivity
- <u>R. Rajput-Ghoshal</u>, F. Lin, T.J. Michalski, V.S. Morozov, M. Wiseman, C. Hutton, "Interaction Region Magnets for Future Electron-Ion Collider at Jefferson Lab", Accepted ORAL Presentation, North American Particle Accelerator Conference (NAPAC'19)

3. Preparation in Progress for Submission

- R. Fair, et al, "Superconducting Magnets for CLAS12", In Progress (JLAB Internal review) for NIM A (Elsevier Publications)
 - Revision 2 in progress after comments from Physics (Daniel and Volker) by 6/27/2019
 - License approval/permission from IEEE (USA) complete and Institute of Physics (UK) in progress (with Rhonda and DeLisa, Legal)

Support for External DOE Reviews

- **FRIB Facility for Rare Isotope Beams (MSU) SC magnet design –** *R. Fair, P. Ghoshal*
- **NSTX-U** National Spherical Torus Experiment Upgrade (PPPL) Resistive coil design R. Fair, R. Rajput-Ghoshal
- □ Mu2e Muon to Electron Conversion Experiment (FNAL) SC magnet design R. Fair
- **MPEX Material Plasma Exposure Experiment (ORNL) SC magnet design** *R. Fair*
- Hi-Lumi LHC High Luminosity Large Hadron Collider (FNAL) SC magnet design R. Fair, P. Ghoshal
- **LSST Large Synoptic Survey Telescope Cryogenics –** D. Kashy
- **US-ITER US Contributions to the ITER Project SC Magnet design –** *R. Fair*

Team Medium – Long term Strategic View

1. MOLLER-Related

- a. Development of tool to translate information from NX CAD models to OPERA (Sandesh, Randy, Probir)
- b. Training on using MAXWELL and ANSYS for structural analysis (*Sandesh*)

2. EIC-Related

- a. Development of design tools to support magnet design iterations (Ruben, Probir, Renuka)
- b. Development of modelling techniques for coil structures (*Eric, Dan*)
- c. Training with LBNL on using ROXIE for accelerator magnet design optimization (*Renuka, Ruben*)

3. General

- a. Mentoring of engineers (*Dave*)
- b. Database of Magnet-Related Design Tools (*Probir*)
- c. Identification (development?) of local shops for 'simple' magnet fabrication projects (*Dave*)

Backup

CRYO – ESR2

Dave Kashy

<u>ESR2 Preliminary Design Review</u> June 19, 2019, 8am-2pm Bld 87, Conference Rm 101 Committee Charge Questions

- 1. Does the thermal dynamic refrigerator model meet the experimental hall refrigeration requirements?
- 2. Have the necessary 4.5K Cold Box refrigerator modifications been identified and defined for detail engineering to proceed?
- 3. Does the Process Flow Diagrams represent all of the subsystems required for the refrigeration system?
- 4. Is there a system/device tag Nomenclature developed which allows the merger and integration of past refrigerator device labeling /drawing/maintenance/vendor documentation into the JLab multiple refrigeration plant system documentation without conflict of labeling duplication and software programming conflicts?
- 5. Has an equipment layout been developed inclusive of control room? Does it account for all major subsystems? Does it allow adequate spacing for operational safety, maintenance and repair?
- 6. Has Process and Instrumentation Diagrams (P&IDs) been developed for each of the subsystems? Are any P&IDs missing or need further engineering?
- 7. Is there a preliminary design for electrical, warm helium, cooling water, and cryogenic piping? Is the preliminary design of the Experimental Hall cryogenic interface appropriate?
- 8. Has long lead procurement items been identified for Q2 FY20?

9. Has the present engineering schedule and status been presented?

- 10. Has a preliminary Failure Mode Analysis been developed?
- 11. Are there any additional preliminary engineering which should be addressed by the design team?
- 12. Does adequate preliminary design exist for the start of detailed engineering?

Committee Members:

Jonathan Creel, <u>creel@jlab.org</u>, Chair

Nate Laverdure, nal@jlab.org

David Kashy, kashy@jlab.org

The committee is charged to evaluate the preliminary engineering status for the End Station Refrigeration System 2 in preparation of detailed engineering to be completed by the fall of 2020. Emphasis should be placed on

- issues of correctness of type and amount of refrigeration to be provided,
- 2. if all subsystems necessary for the operation/ maintenance/ repair of the refrigeration system has been accounted for
- 3. Preliminary documentation used as a baseline for final engineering design

MOLLER

Magnets – Design data translation and control







MOLLER – Coil Model Information Transfer

v1.01 - 05.10.2019

From Jlab: P. Ghoshal, S. Gopinath, R. Fair, D. Kashy, R. Wilson



- 1. OPERA filename Conductors files attached and referenced below for "Segmented Coil JLab"
- 2. OPERA filename Conductors files attached and referenced below for "Hybrid coil JLab"

Note:

- 1. For future information and reference
 - a. The US torus model includes insulation all around the conductor
 - b. DS torus segmented coil model includes insulation all around the conductor
 - c. The DS torus JLab hybrid includes insulation on the sides (to evaluate space and gap between two adjacent coil) and no insulation in the radial direction
- 2. All dimensions are referenced to OLD TARGET location as origin (Note: NOT revised after moving the target by 500 mm downstream)
- 3. Upstream torus are same for both Hybrid and segmented.
- 4. All dims in mm and current density in A/mm^2 (all other units are in SI).
- Typical layout for reference only as per the document titled "MOLLER Toroid Nomenclature definitions document" dated 10/9/2018, D Kashy, R Fair, P Ghoshal, K Kumar, J. Mammei.
- 6. DS Torus: Coil labels Coil A refers to coil on Left looking down stream/beam direction, Sub-coil #1 is upstream, closest to target. Coil A is horizontal.
- 7. Origin (0,0,0) is target center
- 8. The JLab blocky model includes all coil insulation and therefore the outer surface shown in OPERA is the actual physical limit of the coil

JLab *.cond and *.stp files are provided to the collaboration for particle tracking and GEANT analysis



Transferred back to CAD designer to check that the coils are clear of all particle envelopes of interest





Magnet Design

Renuka Rajput-Ghoshal

- Updated the preliminary design of all quadrupoles, skew quadrupoles, solenoids, corrector magnets for Ion and Electron beam lines in the interaction region for the updated lattice file for higher COM energy.
- Working on updating the Interaction Region magnet design part of the p-CDR, magnet design section has been updated, magnet interaction and shielding work is in progress.
- Currently main focus is on iBDS1 and iBDS2, the first two dipole magnets. The iBDS1 has 3 sets of coils and the electron beam line goes through the bore of this magnet, and requires a shielding solution for this magnet. The iBDS2 is a very large bore (800 mm) 4.42 T magnet, examining the design feasibility and option for this magnet - the coil layout for this magnet and some of the deign options are shown in the next slide.
- Investigating design options for 7.6 T cooling solenoid (there are 2 different types of cooling solenoid, one 1.25 m long and 5 T field and other one 2.5 m long and 7.6 T field) and other ICR magnets (current assumption is that 2 x 4m superconducting dipoles, a superconducting sextupole and superconducting quadrupole can be fitted into a single 11.4m long cryostat, present coil design and estimate for other components show that it would require just under 12.2 m of length to accommodate all these requisite elements. Revisiting all the coil length of these magnets again).
- Involved in the Hall C NPS Experiment Readiness Review
- Involved in the review of Injector solenoid spare coils/magnets

Renuka Rajput-Ghoshal

Magnet Design

Detector r	egion ion e	lements											
200 GeV/c	protons												
Element name	Туре	Magnetic Length [m]	Good field radius [cm]	Beam Pipe radius [cm]	Outer Radius [cm]	Dipole Bx	field [T] By	Solenoid [T]	Good field region	Field Homogeneity/ Multipole components	Warm bore/cold bore	Operating temperatute (K)	Thermal shield required (?)
iBDS1a	RBEND	0.75	4	38.5	48.5	0.22	1.32	0	TBD	TBD	Warm	4.5	TBD
iBDS1b	RBEND	0.75	4	38.5	48.5	-0.19	1.32	0	TBD	TBD	Warm	4.5	TBD
iBDS2	RBEND	8.00	4	40.0	90.0	0.00	-4.42	0	TBD	TBD	Warm	4.5	TBD
	Spin Rotator solenoid	2.5	TBD	5				7.64	TBD	TBD	Warm	4.5	TBD
	Spin Rotator solenoid	1.25	TBD	5				4.92	TBD	TBD	Warm	4.5	TBD

EIC

Coil Layout-iBDS2

Renuka Rajput-Ghoshal

Possible options

- Option 1: Current Specification
 - Possible with NbTi only if operating at lower temperature,
- Option 2: Same bore size, same length and reduce the field
 - Field reduced to 3.8 T,
 - Reduced field results in reduced integrated field
- Option 3: Same bore size, reduce the field and increase the length for same integrated field
 - Field is **3.8** T, magnetic length increased for same integrated field,
 - Solution is possible, but magnet coil end-to-end is 10.45 m
- Option 4: Reduce the bore and keep the field and length same
 - Field 4.42 T, magnetic length 8 m, possible solution reduced the coil bore by about 16% (from 400 mm bore radius to 330-340 mm bore radius)



Summery of Possible Options

- 1. Reduced operating temperature
- 2. Reduced Integrated Field
- 3. Increased physical length of the magnet
- 4. Reduced bore

HALL B

SC Magnets Punch list

Ruben Fair

all																							
Versio	n 13.00	PH	YSICS RUNS END																				
Dat	te 06.21.2019					_											_						_
iginee	r R.Fair			s	MI	r w	Т	F	S :	SM	Т	w	TF	s	s	м	τv	N T	F	s	s	м	т
				19	19	5 E	61	19	19	61 61	19	19	61 61	្រុះ	19	19	£ 9	ភ្ន ភ្ន	61	61	61	61	61
				Pr-	p 1		įģ	∱.	Åp.	μ, μ	d,	Apr-	μ γ μ		i ja	, de	de l	à à	- 1	a di	-te	÷.	ż
	Task	Lead	Team	14-1	5 9		- do	-61	50-7	-12	3	24-1	25-1		38	59-7	30-7	2 Z	Σ	Σ-	Σ	9-N	2-N
																				-		_	
1	TORUS - Hall backup power for vacuum pumps SUMMER/FALL 2019	КВ	DA																				
2	TORUS - VT panel replacement with cable disconnect ON HOLD - NEEDS REVIEW	RF	SS	(Drawin	ngs fro	om Fa	cilitie	s have	gone	through	n seve	ral rev	ision	s. Awa	aiting	final v	ersio	n (05.1	17.19)	then	appr	c
3	TORUS - Upgrade PLC firmware from present v27 to ensure compatibility with Windows 10 - COMPLETED 04.23.19	NS	DSG																				
4	TORUS - 'Burp' - COMPLETED 05.31.19	DI	Hall B Techs																				
5	TORUS - Run with solenoid - COMPLETED 04.19.19	PG	RF, NS, DK																				
6	TORUS - MPS water flow control board connectors - Better secure or replace with better connectors COMPLETED 04.26.19	SS	NS, PG	H	https://	/logbc	ooks.j	lab.or	g/entr	y/368	Orde	r Hard	lware										
7	TORUS - Fit better connectors to allow use of control power within MPS. COMPLETED 04.30.19	SS	NS, PG	H	https://	/logbc	ooks.j	lab.or	g/entr	y/368	Orde	r Hard	lware										
8	TORUS - Fit banana plugs to allow easier fitting of phase interlock jumper COMPLETED 04.26.19	SS	NS, PG								Orde	r hard	lware										l
9	TORUS - Link beacons to field in magnet	КВ	Hall B Techs																				
10	TORUS - Raise alarm if COMMs is lost - COMPLETED 4/10/19	NS																					
11	TORUS - Review and move over as many as 'fast dump' triggers to 'controlled ramp' triggers, re-wiring needed (WIRING CHANGES) COMPLETED 05.23.19	RF	NS, SS, PG	0	Change	es agre	eed or	n 04.2	9.19 ai	nd 05.	07.19.	To be	action	ned sh	nortly								
12	TORUS - Review and move over as many as 'fast dump' triggers to 'controlled ramp' triggers, re-wiring needed (PLC CODE CHANGES) COMPLETED 05.23.19	RF	NS, SS, PG																				
3	TORUS - Review and move over as many as 'fast dump' triggers to 'controlled ramp' triggers, re-wiring needed (FPICS CHANGES)	RF	NS SS PG																				
4	TORUS - Review all force limits and whether they should initiate ramp downs or fast dumps, alarms? COMPLETED 04.30.19	DK	NS. RF. PG		No cha	inges r	requir	red. No	oforce	thesh	olds pr	oduce	e fast d	dump	s or c	ontrol	led rar	mp do	wns -	only a	larm	5	
5	TORUS - Force vacuum pumping system gate valves to close when turbo speed fails to about 70%	RF	NS, SS, DA		MPOR	TANT:	Must	t not o	veride	manu	ial cont	trol or	n valve									-	
-			110,00,071																				
1	SQLENOID - Hall backup power for vacuum pumps SUMMER/FALL 2019	кв	DA																				
,	SQLENDID - VT panel replacement with cable disconnect ON HOLD - BUT NEEDS REVIEW	RF	SS																				
,	COLEMPS IN Section 1. Common from a section to 7 to a section of the Western 4.0 COMPLETED 04.23.40	NC	DEC																				
5	SOLENOID - Upgrade PLC IITmware from present V27 to ensure compatibility with windows 10 - COMPLETED 04.23.19 SOLENOID - Bourses enablishus with and without Same at field). COMPLETED 04.10.10	INS INC	DSG DE NE DK																				
•	SULENVID - Reverse polarity run (with and without forus at field) - COMPLETED 04.19.19	PG	RF, NS, DK											-				_				-	-
<u> </u>	SOLENOID - MPS water flow control board connectors - Better secure or replace with better connectors COMPLETED 04.26.19	SS	NS, PG	1	https://	/logbo	ooks.j	lab.or	g/entr	y/368	Orde	r Haro	lware	_					_			_	-
j	SOLENOID - Fit better connectors to allow use of control power within MPS. COMPLETED 04.30.19	SS	NS, PG	ł	https://	/logbo	ooks.j	lab.or	g/entr	y/368	Orde	r Hard	lware	_	_			_				_	_
7	SOLENOID - Fit banana plugs to allow easier fitting of phase interlock jumper COMPLETED 04.26.19	NS	NS, PG								Orde	r Harc	lware	_	_			_					_
\$	SOLENOID - Link beacons to field in magnet	КВ	Hall B Techs																				
	SOLENOID - Raise alarm if COMMs is lost - COMPLETED 4/10/19	NS																					
0	SOLENOID - Review and move over as many as 'fast dump' triggers to 'controlled ramp' triggers, re-wiring needed (WIRING CHANGES) COMPLETED 05.23.19	RF	NS, PG	0	Change	es agre	eed or	n 04.2	9.19 ai	nd 05.	07.19.	To be	action	ned sh	nortly								
1	SOLENOID - Review and move over as many as 'fast dump' triggers to 'controlled ramp' triggers, re-wiring needed (PLC CODE CHANGES) COMPLETED 05.23.19	RF	NS, PG																				
2	SOLENOID - Review and move over as many as 'fast dump' triggers to 'controlled ramp' triggers, re-wiring needed (EPICS CHANGES)	RF	NS, PG																				
.3	SOLENOID - Review all force limits and whether they should initiate ramp downs or fast dumps, alarms? COMPLETED 04.30.19	DK	NS, RF, PG	1	No cha	nges r	requir	red. No	oforce	thesh	olds pr	oduce	e fast d	dump	s or c	ontrol	led rar	mp do	wns -	only a	larm	s	
.4	SOLENOID - Fit small clear plastic (removeable) cover over 24VDC components within PSU cabinet COMPLETED ON 06.04.2019	SS		ł	https://	/logbo	ooks.j	lab.or	g/entr	y/368	5098												
15	SOLENOID - Attach Electrical Hazard warning label to outside of PSU cabinet referencing the 24V DC - complete on 06.04.2019	RF		ł	https://	/logbo	ooks.j	lab.or	g/entr	y/368	5098											_	
5	SOLENOID - Force vacuum pumping system gate valves to close when turbo speed falls to about 70%	RF	NS, SS, DA	1	MPOR	TANT:	: Mus	t not o	veride	manu	ial cont	trol or	n valve	25									
	LV CHASSIS																						
	Where are the two 'spare' chassis? One in working order and the other simply for spares? COMPLETED 04.24.19	BE		E	BRIAN	HAS TH	HESE /	AND W	ILL HA	NG ON	ТО ТН	EM FC		w									
	Compile list (in Excel) to identify all the required drawings and store on O drive (see link above). List to also indicate which vendors to use COMPLETED 04.24.19	RB		E	But sor	me dra	awing	s are s	still mi	issing	or not	uploa	ded to	the r	eposi	tory							
3	Convert list in Item 2 into Hall B document and add to Hall B Document List and also to the document repository COMPLETED 06.21.19	PG		E	But sor	me dra	awing	s are s	still mi	issing	or not	uploa	ded to	the r	eposi	tory							
4	Copy all FPGA software to GITHUB COMPLETED 04.24.19	BE																					
5	Where is the sensor calibration data stored? Should we store this in GITHUB too - does this make sense? COMPLETED 04.24.19	PG		1	M:\hal	lb_eng	g\CLA	S12\M	lagnets	s\Toru	s\JLab	Torus	\C&I_T	Torus	\Cont	rols_8	_Wiri	ng\Ca	librat	ion In	iorma	ition	
6	Where is the spare strain gauge chassis? COMPLETED 04.24.19	КВ		١	WITH K	RISTE	R																
7	Check the Hall B doc list and repository to ensure the strain gauge chassis information and wiring diagrams have been captured. COMPLETED 04.24.19	PG		١	YES - al	ll in re	eposit	tory															
8	Identify all critical spares and costs, should we fabricate some critical components now in case vendors may not provide them in the future? COMPLETED 05.20.19	RB																					
9	Should we build another spare chassis?	RB	PG																				